



Work Safety Alert Ran over by a Reversing Dumper Truck

1. Date of Accident : November 2013

2. Place of Accident: A construction site in Tai Po

3. Summary:

A female worker was run over by a 30-ton dumper truck to death while the truck was reversing along a carriageway under construction.

4. Work Safety Alert for Contractors/Employers:

To prevent workers engaging in road works from being struck by mobile vehicles, contractors/employers should:

- appoint a competent person to conduct risk assessments with particular regard to the operation of the mobile vehicles, the site layout, work environment and traffic control;
- formulate and implement an effective traffic management system which should include the following:
 - > segregating workers from the operating zone of mobile vehicles by suitable barriers;
 - reversising strict access control measures with suitable warning notices in place to avoid unauthorised man-entry into operating zone of mobile vehicles;
 - eliminating reversing where possible, by adopting one way traffic system;
 - > stationing a signaler to give effective signals to vehicle operators who do not have a clear and unrestricted view of its vicinity





especially in reversing motion;

- installing suitable safety devices on the mobile vehicle, such as closed-circuit televisions to enhance the vehicle operator's views especially at the rear and audio/visual alarms for reversing motion to alert persons working nearby, and maintaining the safety devices properly;
- imposing speed limits on traffic routes through erecting speed limit signs and installing speed humps or other similar devices;
- installing appropriate signs and devices to alert vehicle operators that road works is in progress on the site; and
- > ensuring that every worker on the site is wearing a high visibility or reflective vest so that vehicle operators could easily recognize them;
- provide workers with adequate information, training and instruction in respect of the safe system of work for operating mobile vehicle and traffic management measures; and
- implement effective monitoring and supervision to ensure that the above safety measures are strictly followed.

5. Reference:

- Five Steps to Risk Assessment¹
- <u>Safe Systems of Work</u>¹
- A Guide to the Factories and Industrial Undertakings (Loadshifting Machinery) Regulation¹
- <u>Guidance Notes on Safe Use of Loadshifting Machines for Earth Moving Operations on Construction Sites</u>¹

_

¹ Click to view the document





DISCLAIMER

This Work Safety Alert ("the Alert") is issued at the earliest possible opportunity after a serious accident with a view to drawing the attention of interested parties to the general safety precautionary measures necessary to protect people engaging in similar work activities. The material contained in the Alert constitutes general guidance only. It does not reduce, limit, or replace, any legal obligations upon any person to comply with any statutory duties under relevant legislation. Users such as Managers and Supervisors should make their own evaluation of the information contained in the Alert to determine if it can be applied to their own situations and practices. The Labour Department does NOT accept any responsibilities for any loss or damage resulting from the use of or failure to use of the information on the Alert.